

REVISED JANUARY 21, 2016

**BID REQUIREMENTS**

**BID FORM**

To: Savannah-Chatham County Public School System From: CONTRACTOR: \_\_\_\_\_

Re: **Bid #C16-18 (ESPLOST) Construction of Baseball Fields at Beach High School**

**Bid:** Having carefully examined the Bidding Documents describing **Bid #C16-18 (ESPLOST) Construction of Baseball Fields at Beach High School** including all addendums, as well as the site and conditions affecting the Work, bidder hereby proposes to furnish all services, labor, materials, and equipment called for by them for the entire Work, in accordance with the aforesaid documents, for the entire sum of the Work which sum is hereunder called the Bid:

**Item A: Base Bid (Total):** \_\_\_\_\_ Dollars (\$ \_\_\_\_\_ )

**Alternates:** We further propose that, should any of the following alternates be accepted and be incorporated in the Contract, the Bids will be altered in each case as follows: (N/A)

**Receipt of the following Addenda is hereby acknowledged:** # \_\_\_\_\_ # \_\_\_\_\_ # \_\_\_\_\_ # \_\_\_\_\_ # \_\_\_\_\_ # \_\_\_\_\_

**Liquidated Damages:** The bid amount acknowledges the contract date for material completion and an amount of **\$500 per calendar day** for failure to meet the date of material completion.

**Errors or Revisions:** Prior to the bid opening date and hour, errors may be stricken or revisions may be made and corrections entered on this bid form with sufficient clarity to be easily understood. All such annotations shall be made by the authorized representative of the bidder and identified as such. These annotations shall be binding on the bidder. **No revisions will be allowed or accepted on the outside of the envelopes.**

**No Withdrawal:** The bidder and District agree that this bid may not be revoked or withdrawn after the time set for the opening of bids, except as provided in Georgia law, but is an irrevocable offer that shall remain open for acceptance for a period of sixty days following the time set for the opening of bids.

**Execution of the Contract:** If bidder is notified in writing by statutory mail of the acceptance of this bid within thirty five days after time set for the opening of bids, bidder agrees to execute within twenty- one (21) days the Contract for the Work for the above stated Bid, as adjusted by the accepted Alternates, and at the same time to furnish and deliver to the District a Performance Bond and a Payment Bond on forms shown in Section 7 of the General Conditions of the Contract, both in an amount of equal to 100 percent of the Contract Sum.

**Commencement and Completion of Work:** Upon the Effective Date of the Contract, bidder agrees to commence all Preconstruction Activities. Within ten days of the date specified in the Proceed Order, bidder agrees to commence physical activities on the Site with adequate forces and equipment and to **Replace all sod within 120 Days and Material Completion within 240 Days** from the date specified in the Proceed Order and to be 100% complete including all deficiencies within no more than 30 days of Material Completion.

# SCHEDULE OF VALUES

(Revised 1/21/2016)

Item #	Description	Estim. Qty.	Unit Price	Total Price
--------	-------------	-------------	------------	-------------

**PAVING & GRADING**

1.0	General Conditions	JOB	LS		
1.1	Clearing and Grubbing	8.00	AC		
1.2	Remove misc. athletic field equip. (goals posts etc.)	JOB	LS		
1.3	Remove Existing Concrete Curb & Gutter	40	LF		
1.4	Grading and Project Miscellaneous shall include all grading, including off-site removal and replacement of unsuitable material, to meet the finished grades shown on the plans, and project staking, testing, insurance, bonds & all miscellaneous items not included elsewhere in this bid schedule to complete the project in accord with the plans & specifications.	JOB	LS		
1.5	Excavation (13,900 CY)	JOB	LS		
1.6	Borrow (6,500 CY)	JOB	LS		
1.7	Handicap Ramp w/Detectable Warnings	4	EA		
1.8	Concrete Stair and Railing Complete	2	EA		
1.9	Crosswalk Striping	65	LF		
1.1	6" Concrete Bleacher Pad	355	SY		
1.11	4" Thick Concrete Sidewalk	520	SY		
1.12	2' Wide Concrete Swale	140	LF		
1.13	Retaining wall (including sock drain)	250	LF		

**SUBTOTAL**

**STORM DRAINAGE**

2.1	4" HDPE Pipe, smooth bore w/soil-tight joints	55	LF		
2.2	10" HDPE Pipe, smooth bore w/soil-tight joints	90	LF		
2.3	6" Subgrade Drain	4,500	LF		
2.4	Core drill existing curb inlet	1	EA		
2.5	18" RCP CLASS III	45	LF		
2.6	Standard Storm Manhole	1	EA		
2.7	Lower existing grate inlet top	1	EA		
2.8	Convert Existing GI to Manhole	1	EA		
2.9	Inline Drain	2	EA		

**SUBTOTAL**

Item #	Description	Estim. Qty.	Unit Price	Total Price
--------	-------------	-------------	------------	-------------

<b>EROSION CONTROL</b>				
3.1	Silt Fence - Type "S" Double Row	1,900	LF	
3.2	Silt Fence - Type "S" Single Row	280	LF	
3.3	Stone Check Dam	2	EA	
3.4	Tree Protection Barricade	4	EA	
3.5	Sedimentation & Erosion Control shall include all items not specifically listed.	JOB	LS	
3.6	Construction Exit w/ Concrete Washout	2	EA	
3.7	Temporary Sediment Trap	6	EA	
3.8	Permanent Grassing-Hydroseeding (not including sod)	6	AC	
3.9	Inlet Sediment Traps	5	EA	
3.1	Matting Blanket (Mb)	31,000	SF	
3.11	Pig in a Blanket (Sd2-P)	4	EA	
3.12	NPDES Permit Compliance (include inspections, reporting and record keeping)	JOB	LS	

**SUBTOTAL**

<b>MISCELLANEOUS FIELD CONSTRUCTION</b>				
4.1	Scoreboard Complete	2	EA	
4.2	Site Electricity	JOB	LS	
4.3	Grassing (SOD)	124,100	SF	
4.4	4" Root Zone Mix	1,500	CY	
4.5	12" Free Draining Fill	5,800	CY	
4.6	Laser Grading Sportfield	JOB	LS	
4.7	Clay Infield (Including Bullpens)	21,100	SF	
4.8	Warning Track	20,000	SF	
4.9	6' Chainlink Fence (including gates and hardware)	1,600	LF	
4.1	10' Chainlink Fence (including gates and hardware)	480	LF	
4.11	24' High Backstop	280	LF	
4.12	Dugout (Complete)	4	EA	
4.13	Softball & Baseball Pitchers Plate Including Mounting System	2	EA	
4.14	Bases Including Mounting System	6	EA	
4.15	Outfield Distance Signs	6	EA	
4.16	Home Plate Including Mounting System	2	EA	
4.17	Aluminum Bleachers Complete	JOB	LS	
4.18	Foul Pole	4	EA	
4.19	Stripe Field	JOB	LS	

**SUBTOTAL**

Item #	Description	Estim. Qty.	Unit Price	Total Price
--------	-------------	-------------	------------	-------------

<b>WATER DISTRIBUTION SYSTEM</b>				
5.1	Irrigation System (Complete)	JOB	LS	
5.2	Remove Existing Water meters, Backflow Preventers, Vaults, Enclosures, Valves, Spiggots and Appertenances	JOB	LS	
5.3	Relocate existing fire hydrant	1	EA	
5.4	Adjust 6" fire hydrant PVC lead to provide 3' of cover	JOB	LS	
5.5	Connect to existing irrigation service (including controls)	2	EA	
5.6	1" Polyethylene Service Lateral	700	LF	
5.7	1" Corporation Stop	1	EA	
5.8	3/4" Polyethylene Water Service	170	LF	
5.9	3/4" Gate Valve in Box	1	EA	
5.10	Yard Hydrant w/Key Lock	2	EA	
5.11	3/4" Hose Bib/Box	1	EA	
5.12	Remove & Relocate existing Water Meters, BFPs, Vaults, Enclosures, Valves, Valve Boxes, Hydrants, FDCs and Pipe (as shown)	JOB	LS	
5.13	2" PVC Waterline	185	LF	
5.14	2" Meter & Backflow Preventor in Vault	1	EA	
5.15	10" X 2" Tapping Sleeve and Valve in Box	1	EA	
5.16	2 Gate Valve and Box	2	EA	
5.17	Lockable Frost-Proof Hydrant and Riser	1	EA	
5.18	2" Trenchless Crossing	Job	LS	

**SUBTOTAL**

<b>PAVING &amp; DRAINAGE</b>	<input style="width: 100%; height: 20px; border: 1px solid black;" type="text"/>
<b>STORM DRAINAGE</b>	<input style="width: 100%; height: 20px; border: 1px solid black;" type="text"/>
<b>EROSION CONTROL</b>	<input style="width: 100%; height: 20px; border: 1px solid black;" type="text"/>
<b>MISCELLANEOUS FIELD CONSTRUCTION</b>	<input style="width: 100%; height: 20px; border: 1px solid black;" type="text"/>
<b>WATER DISTRIBUTION SYSTEM</b>	<input style="width: 100%; height: 20px; border: 1px solid black;" type="text"/>

**TOTAL**