

Purchase and Installation of a Cooling Tower at East Broad K-8 School
Number: BID C16-10 (ESPLOST)
Posting Date: 09/06/15 12:00 P.M.
Addendum # 1
Closing Date: 09/15/15
Time: 2:00 P.M.

ADDENDUM NO. 1: BID C16-10 (ESPLOST) PURCHASE AND INSTALLATION OF A COOLING TOWER AT EAST BROAD K-8 SCHOOL

The information contained in this document shall become an official part of the original document and shall be acknowledged as noted on the Certification Form of the Invitation to Bid solicitation document. Failure to acknowledge receipt of an addendum may result in status of non-responsive. Firms are encouraged to review the contents of this document and to respond accordingly.

Addendum No. 1 is hereby issued to Provide Specification Clarifications, to respond to all requests for clarification and request for material substitution(s), and to provide a Register of Firms in attendance at the Pre-Bid Conference conducted on September 1, 2015. All documents referenced herein are available to view and print directly from the District's website in the "supporting docs" file.

- 1. A COPY OF THE REGISTER OF FIRMS IN ATTENDANCE AT THE PRE-BID CONFERENCE AND SITE VISITATION CONDUCTED ON SEPTEMBER 1, 2015 IS AVAILABLE TO VIEW AND TO PRINT DIRECTLY FROM THE DISTRICT'S WEBSITE. ALL ADDENDUM DOCUMENTS ARE LOCATED IN THE "SUPPORTING DOCS" FILE.**
- 2. CLARIFICATION SECTION 4.0 EQUIPMENT SPECIFICATIONS (Attachment "A"; Page 2, 4.0; Motor; 2nd Sentence): Delete "1800 or". Motor will be two(2) speed- 1800/900 RPM.**
- 3. CLARIFICATION SECTION 4.0 EQUIPMENT SPECIFICATIONS (Attachment "A"; Page 3, 4.0; Starter): Delete "NEMA 3R". Starter is Crossfire 2-Speed.**
- 4. CLARIFICATION SECTION 5.0 SCOPE OF WORK REQUIREMENTS (Attachment "A"; Page 3): The District Reserves the right to retain ownership of and to request the Contractor to remove any part or accessory off of the existing Cooling Tower system or control panel.**
- 5. CLARIFICATION SECTION 5.0 SCOPE OF WORK REQUIREMENTS (Attachment "A"; Page 3; 1st Paragraph; 1st Sentence): The Contractor will be responsible for removing and installing a "new" security fence around unit if the existing fence is damaged by the Contractor while performing the work required under a resulting contract.**

6. A COPY OF THE DISTRICT'S RESPONSE TO ALL REQUESTS FOR CLARIFICATION (Addendum 1 Q&A) IS AVAILABLE TO VIEW AND TO PRINT DIRECTLY FROM THE DISTRICT'S WEBSITE. ALL ADDENDUM DOCUMENTS ARE LOCATED IN THE "SUPPORTING DOCS" FILE.

7. THE FOLLOWING ITEMS HAVE BEEN APPROVED AS ACCEPTABLE MATERIAL SUBSTITUTIONS:

Baltimore Aircoil Co., Inc. 640 GPM (cooling tower pump flow), 95 entering, 85 leaving, 80 wetbulb. Unit footprint is 8' x 12' (nominal).

*****All other terms and conditions of the bid remain unchanged*****

END OF ADDENDUM NO. 1