

**Southwest Elementary School Canopy Extension
Number: BID C18-20
Addendum # 1**

The information contained in this document shall become an official part of the original document and shall be acknowledged as noted on the Certification Form (Form 1) of solicitation document and the Bid Form (Form 10) in the space provided. Failure to acknowledge receipt of an addendum may result in a status of non-responsive. Firms are encouraged to review the contents of this document and to respond accordingly.

Addendum No. 1 is being issued to schedule a second mandatory pre-bid meeting. A mandatory pre-bid meeting is scheduled for Thursday, February 15, 2018 at 1:00 pm. Bidders should meet at the front entrance of the facility. Bids will not be accepted from any firm that is not represented at the mandatory pre-bid meeting and site visitation.

The date for submittal of request for interpretations and request for approval of substitute products is extended to close of business on Tuesday, February 20, 2018.

The bid closing date is extended until Thursday, March 1, 2018 at 11:00 am.

Addendum No. 1 also provides a revised Attachment A: Project Description and Scope of Work

*****ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED*****

End of Addendum #1 to Bid C18-20 Southwest Elementary School Canopy Extension

Attachment A

Project Description:

Maintenance and Operations Department of the Savannah-Chatham County Public School System is seeking a turn-key contractor to add approximately 620 square feet of matching/comparable aluminum walkway cover at Southwest Elementary School. The school is located at 6020 Ogeechee Road, Savannah, GA. 31419. This work needs to be done while the campus is occupied and completed in ninety (90) days. This project will connect to an existing Perfection Architectural Systems canopy that was installed as part of the original school construction. New system shall be factory fabricated (welded aluminum frame) and connect to the existing canopy to provide continuity. The materials and sizing to be in accordance with information and specifications contained in the document listed below and attached photos.

In the event that a contractor is offering other than stated in the specifications, the contractor must provide complete technical information, specifications, manufacturer's name, model number and a complete list of deviations to the District for approval. The burden of proof for documenting equivalency rests with the contractor. All determinations for acceptability of equal or alternate materials shall rest with District staff and their decision is considered final.

All workers shall comply with SCCPSS policies and regulations (e.g.: no tobacco, no loud radios, no use of alcohol, firearm free, etc. *anywhere* on SCCPSS property) as listed on the District website (www.sccpss.com).

Scope of Work:

Fabricate and install approximately 14'0" x 44'0" Gable Style Extruded Aluminum Walkway Cover attached to end of existing. Style and Location as shown in photos. Project shall include design, engineering and installation of canopy, and modification/coring of existing sidewalk to accept new canopy support system. Addition of new sidewalk to be performed by others.

MATERIALS

- a. Columns: 4" x 6"
- b. Beams: 4" x 4" / 4" x 6"
- c. Decking: 3" x 6" x .060" Rigid Roll Lock
- d. Fascia: 4" x 8" Gutter.
- e. Finish - 2-coat Kynar, standard colors. Match existing colors to best extent possible.

ENGINEERING

- a. All engineering, permitting dig location shall be performed to meet all local, state and federal codes.
- b. Work will be done on an occupied campus. Safety barriers and site coordination will be necessary.

MANUFACTURERS

- a. Perfection Architectural Systems
- b. Mitchell Metals
- c. Peachtree Protective Covers